



Notes:

1. The shelf cut outside the top of the trench shall be a min. of 12" from the edge of the top of trench, and the shelf cut shall run parallel or perpendicular to the center line of the roadway, for the entire length of the project, and ending with a cut a min. of 12" past the end of the trench. (See R-12A)
2. Aggregate base course shall be a min. of 8" of compacted VDOT 21A stone or match the existing stone base, which ever is thicker.
3. Asphalt shall be a min. of 2" and, if the existing asphalt is thicker, the additional thickness of asphalt placed as either SM-9.5 up to 3" or BM-25.0.
4. SM-9.5A for Local Streets. SM-9.5D for all others
5. Pavement markings shall be replaced as needed.
6. If centerline of parallel utility is within 4 feet of curb, patch shall be extended to curb.